



SECTION A-A

**TYPICAL CONSTRUCTION AROUND ALL
VALVE BOXES EXISTING AND PROPOSED**

NOTES:

1. KEEP ALL VALVES AT STONE GRADE OR LOWER FOR INSTALLATION OF ITEMS 301 AND ITEM 448. THEN AFTER ITEM 301 AND ITEM 448 INTERMEDIATE AND SURFACE COURSE ARE INSTALLED, RAISE TO 1/4" BELOW FINAL SURFACE.

ADDITIONAL WORK AND CONCRETE TO DO THIS WORK SHALL BE INCLUDED IN THE COST OF THE VALVE OR VALVE ADJUSTED TO GRADE.

VILLAGE OF
ADA

CHOICE
ONE ENGINEERING

WATER VALVE ADJUSTED TO GRADE

REVISIONS:

DATE
APPROVED:
NOV. 2011

PAGE No.

800-25